SCHEDULE A

Asset	ACTIVE STORM	POST STORM		
		6-Hours	12-Hours	48-Hours
Arterial Roads	Anti-icing may be applied before the storm. Both lanes are actively maintained but may be snow-covered. Anti-icing is applied at steep grades (more than 7%) and arterial intersections.	Both lanes are plowed; bare asphalt may be showing.	Both lanes are cleared to bare asphalt.	
Collector Roads	Anti-icing may be applied before the storm. A single access lane is cleared at regular intervals to provide access to arterial roads. Anti-icing is applied at steep (more than 7%) grades and intersections.	Both lanes have been plowed but remain snow-packed.	Both lanes are cleared, bare asphalt may be showing	Both lanes are cleared to bare asphalt
Local Roads	Anti-icing may be applied before the storm.		Both lanes have been serviced, but remain snow-packed. De-icing material may be applied.	Both lanes are cleared, with some bare asphalt showing.
Arterial Sidewalks	Anti-icing may be applied before the storm. A minimum of 1.0m of sidewalk is maintained as well as cross-cuts. The surface may be snow-covered and cross-cuts snow-packed. Anti-icing is applied at steep grades (7%) and intersections.	A minimum of 1.2m of sidewalk is maintained, as well as cross-cuts. Surface plowed, with some bare sidewalk showing and snow-covered crosscuts.	Full width of sidewalk is plowed (less street windrow), as well as cross-cuts. Surface is, and cross-cuts are bare.	

DRAFT

SCHEDULE A (continued)

Collector Sidewalks	Anti-icing may be applied before the storm. Typically snow-packed.	A minimum of 1.0m of sidewalk is maintained as well as cross-cuts. The surface may be snow-covered and cross-cuts snow-packed.	A minimum of 1.2m of sidewalk is maintained, as well as cross-cuts. Surface generally cleared, with some bare sidewalk showing and snow-covered crosscuts.	Full width of sidewalk is maintained, as well as cross-cuts. Surface is, and crosscuts are bare.
Local Sidewalks	Anti-icing is applied before the storm. Generally, snow-packed.	Generally, snow-packed.	A minimum of 1.2m of sidewalk is maintained as well as cross-cuts. The surface may be snow-covered and cross-cuts snow-packed.	Full width of sidewalk is maintained, as well as cross-cuts. Surface generally cleared, with some bare sidewalk showing and snow-covered crosscuts.
Public Works Garage (including Hank Snow Drive)	Maintain access to entrances, including garage bays, as well as access to fuel pumps and de-icing materials. Surfaces may be snow-covered.		Access to entrances, including garage bays, and parking as well as access to fuel pumps and de-icing materials. Surfaces are bare on asphalt and snow packed in gravel.	Access around sewer lagoons
Hillsview Acres	As outlined in the current snow clearing and removal agreement			
Municipal Services Building	Access to apparatus bays, the ancillary building, as well as parking stalls along Henry Hensey Drive. Surfaces may be snow covered.			

DRAFT

SCHEDULE A (continued)

Municipal Administration Building	The parking lot on the South side of White Point Rd and the front walkways should be serviced regardless of office closure. Surfaces may be snow covered.		All asphalt parking lots are serviced, with some bare asphalt showing. All entrances and sidewalks cleared with some bare surfacing.	All asphalt parking lots are serviced, with some bare asphalt showing. Gravel parking lot is snow packed. All entrances and sidewalks cleared with some bare surfacing.
Liverpool Business Development Centre	Priority parking sections as identified in Schedule B to be plowed, and entrances and exits to be maintained to allow egress. Surfaces will be snow-covered.	Priority parking section (Schedule B) are serviced, with some bare asphalt showing. All entrances and sidewalks cleared with some bare surfacing.		Entire parking lot is serviced, with some bare asphalt showing. All entrances and sidewalks cleared with some bare surfacing.
Queens Place Emera Centre	Priority parking sections as identified in Schedule B to be plowed, and entrances and exits to be maintained to allow egress. Surfaces will be snow-covered.	Priority parking section (Schedule B) are serviced, with some bare asphalt showing. All entrances and sidewalks cleared with some bare surfacing.	Entire parking lot is serviced, with some bare asphalt showing. All entrances and sidewalks cleared with some bare surfacing.	
Ground Search & Rescue	Priority parking sections as identified in Schedule B to be plowed. Surfaces will be snow-covered.	Priority parking section (Schedule B) are serviced and remain snow covered.		Entire parking lot are serviced but may remain snow packed.
Town Hall Arts & Cultural Centre	Front sidewalk to be serviced. Surface will be snow covered.		Front sidewalk to be cleared with some bare surfacing. Entrances and exits to be cleared during RQM regular business hours. Parking lot cleared but snow covered.	The entire parking lot is serviced, with some bare asphalt showing. All entrances and sidewalks cleared to bare surface.

DRAFT

SCHEDULE A (continued)

Downtown Parking	Priority parking sections, as identified in Schedule B to be plowed. Surfaces will be snow-covered.		The entire parking lot is serviced, with some bare asphalt showing.	
Queens Waste Management Facility	Parking near the maintenance garage is cleared, as well as the main road and scales, public drop off and leachate pond. Surfaces will be snow-covered.		Parking near the maintenance garage is cleared, as well as the main road and scales, public drop off and leachate pond. Gravel surfaces will be snow-packed.	
Pine Grove Park				Parking area at Milton Rd plowed. Gravel surfaces will be snow-packed.
Community Waste Collection Sites ('Grey Boxes')				Access to bins cleared. Surface may be snow-covered or snow-packed. Apply traction
Dry Hydrants				Access road and turning point cleared around the hydrant head. Surface may be snow-covered or snow-packed.

DRAFT

Sandy Cove
Liverpool Harbour
Fort Point
Liverpool
Liverpool Town Hill National Historic Site of Canada
Queens General Hospital
Old Falls Rd
Hillcrest Rd
Bristol Ave
Hunts Cove Dr
Hunts Cove Rd
Hwy 3
Hwy 8
Hwy 103
Exit 8
Exit 9
Exit 10
Exit 11
Exit 12
Exit 13
Exit 14
Exit 15
Exit 16
Exit 17
Exit 18
Exit 19
Exit 20
Exit 21
Exit 22
Exit 23
Exit 24
Exit 25
Exit 26
Exit 27
Exit